

- CONTRACTOR TO GROUND AND PROVIDE SURGE PROTECTION FOR FIELD UNIT IN ACCORDANCE W/ MANUF. RECOMMENDATIONS AND GROUND ROD SHOWN (SEE DETAIL). CONTRACTOR SHALL INSTALL A 20A NON-FUSED DISCONNECT AND 120V DUPLEX RECEPTACLE INSIDE PEDESTAL.
- INSTALL CONTROLLER PER MFG. PRINTED INSTRUCTIONS AND PER LOCAL CODES. LOCATION SHOWN ON DRAWINGS OR APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO CONSTRUCTION.

PROVIDE PRE-WIRED UL LISTED CONTROLLER ASSEMBLY.



## **DEPARTMENT OF PUBLIC WORKS**



STANDARD DETAIL

DATE: 1/3/24 DRAWN BY: IJPC

OF

1

SHEET: 1

PROWAG AND DOWNTOWN PROJECTS

**IRRIGATION CONTROLLER**