


SOIL CELL NOTES :

1. AVOID ALL OBSTRUCTIONS. COORDINATE WITH UTILITY INSTALLATION
2. PRIOR TO BEGINNING WORK, CONTRACTOR TO INVENTORY EXISTING CONDITIONS AND EXISTING UTILITY LOCATIONS. CONTRACTOR TO PROTECT IN PLACE EXISTING UTILITIES. CONTRACTOR TO USE CAUTION. CALL BEFORE YOU DIG AND CALL BEFORE YOU OVER HEAD
3. PROTECT IN PLACE ALL TREES AND LANDSCAPE ADJACENT TO AND OUTSIDE LIMITS OF PROJECT IMPROVEMENTS. CONTRACTOR SHALL REPLACE ALL PLANTS DAMAGED DUE TO CONSTRUCTION WITH PLANTS OF THE SAME GENUS, SPECIES, VARIETY, SIZE AND FORM AT THE CONTRACTOR'S EXPENSE.
4. CONTRACTOR TO VERIFY THAT THE EXISTING TREES TO REMAIN WILL NOT BE DAMAGED BY DEMOLITION OR CONSTRUCTION. IF ANY ARE IN DANGER, IDENTIFY THEM AND NOTIFY THE OWNER'S REPRESENTATIVE
5. BRING ANY DISCREPANCIES TO THE OWNER'S REPRESENTATIVE'S ATTENTION IMMEDIATELY
6. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL QUANTITIES
7. ADD PRE-EMERGENT HERBICIDE ABOVE AND BELOW MULCH



PROWAG AND
DOWNTOWN PROJECTS

SOIL CELL
CROSS SECTION

DEPARTMENT OF PUBLIC WORKS
CAPITAL PROJECT MANAGEMENT

DATE: 1/30/24 DRAWN BY: CP

SHEET: 1 OF 1

