

- NOTES 1. AL ALL FABRICATED METAL COMPONENTS SHALL BE STEEL SHOTBLASTED, ETCHED, PHOSPHATIZED, PREHEATED, AND ELECTROSTATICALLY POWDER-COATED WITH T.G.I.C. POLYESTER POWDER COATINGS. PRODUCTS SHALL BE FULLY CLEANED AND PRETREATED, PREHEATED AND COATED WHILE HOT TO FILL CREVICES AND BUILD COATING FILM. COATED PARTS SHALL THEN BE FULLY CURED TO COATING MANUFACTURER'S SPECIFICATIONS. THE THICKNESS OF THE RESULTING FINISH COAT AVERAGES 8-10 MILS.
- IT IS NOT RECOMMENDED TO LOCATE ANCHOR BOLTS UNTIL BENCH IS IN PLACE. PERMANENTLY AFFIX TO THE GROUND. CONSULT YOUR LOCAL CODES FOR REGULATIONS.
- ANCHOR BOLTS TO BE PROVIDED BY CONTRACTOR.

DEPARTMENT OF PUBLIC WORKS

STANDARD DETAIL

DATE: 6/12/19 DRAWN BY: UPC

> SHEET: 1 OF

PROWAG AND DOWNTOWN PROJECTS

DOWNTOWN STEEL BENCH